


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-065-01328-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Graham County. Sec. 2 Twp. 8S Rge. (E) 24 (W)  
Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 SE/r  
Lease Owner Barnett Oil Company  
Lease Name Lyon Well No. 1  
Office Address 411 First Nat'l Bank Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 19\_\_  
Application for plugging filed October 28, 1970  
Application for plugging approved October 29, 1970  
Plugging commenced January 28, 1971  
Plugging completed January 28, 1971  
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3795 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3794'	1026.52'
				8 5/8"	123'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom plug back with sand to 3600'. Sanded back from 3600' to 3575'.  
Mixed and ran 5 sacks cement thru dump bailer.  
Pulled tubing to 1000'; mixed 20 sacks gel; circ; pulled 1 jt. to 970'; mixed  
100 sacks cement - 50-50 Posmix, 6% gel - pumped out. Pulled tubing to 240';  
mixed 75 sacks cement; circ. out the top.

Job completed @ 5:30 P.M.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 10 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
3/10/71

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co.  
Address P. O. Box 522, Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Jack S. Griggs, (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) Jack S. Griggs  
411 First Nat'l Bank Bldg., Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of March, 1971

My commission expires February 27, 1972.

Mildred F. Willis, Notary Public.



15-065-01328-00-00

BARNETT OIL CO.

10-29-70

LYONS #1 SESE-SE, Sec 2-8-24W Graham County

0-20 Surface Clay

20-30 HARD Green sand.

30-70 Sand.

70-110 Blue shale

~~110-110~~ Ran 110' of 8 3/4 casing cemented w/ 100 sac. CIRC

110-200 shale Red bed.

200-700 shale

700-1310 Shale & shells

1310-1600 Sand Red bed & shale

1600-1985 Red bed & shale

1985-2035 Anhydrite

2035-2290 shale & shells

2290-2460 chert, lime & shale

2460-2990 lime & shale

2990-3795 lime.

Ran 2736' of 5 1/2" - 17# - 11 1/2" & third - ~~top~~ lap weld on  
Bottom & 1062' 5 1/2" - 17# SS. 8' on top. cemented  
w/ 100 sac.

Plug back TD 3788.

Per. with 100 holes 3620 to 3780.

yours Truly  
Deane O. Sharpe

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 29 1970  
CONSERVATION DIVISION  
Wichita, Kansas

10/29/70