

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-02224-00-00

7/18/58

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
311 No. Broadway
Wichita, Kansas

Osage County, Sec. 2 Twp. 6S Rge. 24 (E) W (W)

Location as "NE/CNWSW" or footage from lines NW SE NW SE

Lease Owner Kaiser-Francis

Lease Name Welby Well No. 1

Office Address Ellinwood, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____

Plugging commenced July 7 1958

Plugging completed July 12 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A.D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	224'	none
				5 1/2	3848'	3063'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from 3700' to 3660'. Mixed and dumped 5 sx. cement from 3660' to 3620'. Pulled 5 1/2. Mudded from 3620' to 220'. Set 10' rock bridge from 220' to 210'. Mixed and dumped 25 sx. cement from 210' to 135'. Mudded from 135' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. cement from 30' to base cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1958
CONSERVATION DIVISION
Wichita, Kansas
2/27/58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ACE PIPE PULLING CO.

Address Box 304 GREAT BEND, KS.

STATE OF Kansas, COUNTY OF Barton, ss.

I, W. J. Hall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Hall

(Address) _____

SUBSCRIBED AND SWORN to before me this 16 day of July, 1958

Delmer L. Poston

Notary Public.

My commission expires _____

PLUGGING
FILE SEC. 2 T. 8 R. 24
BOOK PAGE 111 LINE 16

15-065-02224-00-00

DRILLER'S LOG

COMPANY:
CONTRACTOR:
FARM:
LOCATION:

KAISER-FRANCIS
LEBEN DRILLING, INC.
WELTY #1
1/4 SEC 2 1/4 W 1/4 SEC 2-8S-24W
GRAHAM COUNTY, KANSAS
JUNE 9, 1958
JUNE 18, 1958

COMMENCED:
COMPLETED:

0	224	Shale	
224	820	Shale & Shells	<u>LOG TOPS:</u>
820	1435	Shale & Shells	
1435	1985	Shale	Hegbner 3562
1985	2015	Anhydrite	Toronto 3585
2015	2470	Shale & Shells	Lansing 3595
2470	2725	Shale	Bs. K.C. 3810
2725	2940	Shale & Shells	
2940	3560	Shale & Lime	Elevation 2397 K.B.
3560	3650	Lime	
3650	3750	Lime	
3750	3810	Lime	
3810	3850	Shale	
		<u>Rotary Total Depth</u>	

Set 224° of 8 5/8" surface casing with 150 sacks cement & 2% CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Welty #1, located 1/4 SEC 2 1/4 W 1/4 SEC 2, Township 8 South, Range 24 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: s/Frank Hamlin

STATE OF KANSAS)

SS:

~~COUNTY OF SEDGWICK~~

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 24th day of June, 1958.

s/Ruth N. Benjamin
Ruth N. Benjamin, Notary Public

My Commission Expires
June 27, 1961

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1958

CONSERVATION DIVISION
LUBBOCK OFFICE

PLUGGING
HL SEC 2 T 8 R 24W
BOOK PAGE 111 LINE 16