


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

15-045-00862-0058  
WELL PLUGGING RECORD

GRAHAM County. Sec. 3 Twp. 8 Rge. 24 (E) (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE  
Lease Owner R. W. SHIELDS, BARNETT AND EMPIRE DRILLING COMPANY  
Lease Name EVANS Well No. 1  
Office Address 400 BROWN BUILDING, WICHITA 2, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed JULY 19 19 56  
Application for plugging filed JULY 19 - VERBAL 19 56  
Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_  
Plugging commenced JULY 19 19 56  
Plugging completed JULY 19 19 56  
Reason for abandonment of well or producing formation DRY HOLE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MILTON GALYARDT  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3830 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	175'	CEMENTED

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

BOTTOM PLUG SET AT 196' WITH 15 SACKS CEMENT.  
TOP PLUG SET AT 40' WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY  
Address 400 BROWN BUILDING, WICHITA 2, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
I, DAN J. KORNFELD (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) [Signature]  
DAN J. KORNFELD  
400 BROWN BLDG., WICHITA 2, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 24TH day of JULY, 1956

My Commission Expires Oct. 21, 1958

My commission expires \_\_\_\_\_

[Signature]  
Notary Public.



PLUGGING  
FILE SEC 3 T 8 R 24W  
BOOK PAGE 92 LINE 32

1956  
CONSERVATION DIVISION  
Wichita, Kansas

7/25/56

15-065-00862-0000

LOG

COMPANY: R. W. SHIELDS, BARNETT AND EMPIRE DRILLING COMPANY

CONTRACTOR: EMPIRE DRILLING COMPANY

FARM: EVANS NO. 1

LOCATION: SE SE SE OF SEC. 3-8-24, GRAHAM COUNTY, KANSAS

COMMENCED: JULY 11, 1956

COMPLETED: JULY 19, 1956

ELEVATION: 2345 K.B.

-----						
0	TO	196	SHALE AND SAND	TOPS:		
196	TO	1610	SHALE AND SHELLS			
1610	TO	1991	SHALE AND SAND	ANHYDRITE	1991	+ 354
1991	TO	2015	ANHYDRITE	HEEBNER	3572	-1227
2015	TO	2685	SHALE AND SHELLS	TORONTO	3591	
2685	TO	2985	SHALE AND LIME	LANSING KANSAS CITY	3611	-1266
2985	TO	3062	LIME AND SHALE	BASE KANSAS CITY	3818	
3062	TO	3315	SHALE AND LIME			
3315	TO	3390	LIME AND SHALE			
3390	TO	3545	SHALE AND LIME			
3545	TO	3605	LIME AND SHALE			
3605	TO	3790	LIME			
3790	TO	3830	LIME AND SHALE			
3830			R.T.D.			

DRY AND ABANDONED

CASING: RAN 175 FT. OF 8 5/8" AND CEMENTED WITH 115 SACKS CEMENT.

D.S.T. NO. 1 3628-49 OPEN 1 HOUR. WEAK-FAIR BLOW FOR 1 HOUR. SHUT IN 20 MIN. RECOVERED 110 FT. MUDDY SALT WATER. NO OIL. BHP 1090#.

D.S.T. NO. 2 3748-64 OPEN 30 MIN. WEAK BLOW FOR 3 MIN. BY-PASSED TOOL. SHUT IN 15 MIN. RECOVERED 15 FT. MUD. NO OIL. BHP 30#.

-----  
I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE EVANS NO. 1, SE SE SE OF SEC. 3-8-24, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.



*Dan J. Kornfeld*  
\_\_\_\_\_  
DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME, A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 24TH DAY OF JULY, 1956.

*Lucille Han*  
\_\_\_\_\_  
NOTARY PUBLIC

MY COMMISSION EXPIRES My Commission Expires Oct. 21, 1958

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 25 1956

7/25/56

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 3 T 8 R 24W  
BOOK PAGE 82 LINE 32