

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-01331-00

LEASE NAME Miron Goff "A" #1

WELL NUMBER _____

SPOT LOCATION C. SW. SE. NW/4

SEC. 3 TWP. 8 RGE. 24W (E) of W

COUNTY Graham

Date Well Completed _____

Plugging Commenced 5/25/84

Plugging Completed 6/1/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling bought from Tomlinson Oil Co., Inc.

ADDRESS Box 1588, Great Bend, Ks. 67530

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3765'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	158'	none
				5 1/2"	3763'	386'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with 5 sacks cement, sand to 3525', & 5 sacks cement. Had bridge at 420'. Shot pipe at 390'. Pulled 12 joints of pipe. Plugged well with 2 hulls, 1 gal. 100 cement, 12 gal. 8 5/8 plug, & 70 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

STATE OF KANSAS RECEIVED
CORPORATION COMMISSION
6/1/84 JUN 11 1984
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1984



Irene Hoover
NOTARY PUBLIC

My Commission expires _____

15-065-01331-0000
 ROTARY DRILLER'S LOG

E. K. Carey Contractor
 Box 620
 McPherson, Kansas

Elevations: 2297 K.B.
 2294 D.F.
 2292 Gr.

Miron Goff "A" #1

8-5/8" x 5 1/2" Head 6.70'
 below K. B.

C, SW SE NW/4
 Sec. 3-8-24W
 Graham County, Kansas

Casing Record:

Well Commenced: 9-30-54
 Well Completed: 10-12-54

8-5/8" @ 158' w/85 sks.
 5-1/2" 3763' w/100 sks.
 Pozmix Cement

Contractor: E. K. Carey Contractor, Rig #1, Box 620, McPherson, Kansas
 Geologist: Don Hollar, E. K. Carey Drlg. Co., 815 Central Bldg. Wichita

Figures Indicate Bottom of Formation K. B.

Cellar	7
Shale	30
Sand	40
Shale	158
Shale and shells	700
Shale and shells	940
Sand and shale	1250
Shale and shells	1410
Shale, shells & Red Bed	1500
Sand	1680
Shale, red bed & lime shells	1780
Lime and shale	1945
Lime	1995
Lime and shale	2075
Lime and shale	2180
Lime and shale	2305
Shale and lime	2545
Lime and shale	2870
Lime	3120
Lime and shale	3220
Shale and lime	3345
Lime and shale	3430
Lime	3765 TD

Geologist Tops:

Heebner	3504
Lansing	3523
Oil shows	3573, 79, 3683-87 & 3698-3705
Centralizers @	3716, 3670, 3590 and 3560
Base K.C.	3744
Rotary Total Depth	3765
5 1/2" set	3763 or 2' off bottom
DST - 3557-3591	or 34' anchor. Tool open 1 hr. with strong blow. Closed 20 M. for BHP. Gas to surface in 1 hr. Rec. 2630' gassy oil, no water. BHP 1190# FFP 578# IFF 110#.
DST - 3592 - 3630	or 38' anchor. Tool open 1 hr. 15 M. Weak blow, but increased Closed 20 M for BHP. Rec. 1060' muddy salty water. BHP 1010# FFP 420#.
DST - 3675 - 3707	or 32' anchor. Tool open 1 hr. with strong blow thru out test Closed 20 M for BHP. Rec. 1980' gas 530' gassy oil, no water. BHP 950# FFP 80#.
DST - 3707 - 3728	or 21' anchor. Tool open 30 M. with no blow. Rec. 5' mud. BHP 350#.

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 15th day of October, 1954

E. K. CAREY CONTRACTOR

BY Herbert Rhoton
 Herbert Rhoton, Superintendent

Edw. J. ...
 NP

My Commission Expires: November 13, 1956