

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-01332-00-00

LEASE NAME Miron Goff "A" #2

WELL NUMBER _____

SPOT LOCATION C NW SE NW/4

SEC. 3 TWP. 8 RGE. 24w(E) (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 5/22/84

Plugging Completed 6/1/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kelso Casing Pulling bought from Tomlinson Oil Co., Inc.

ADDRESS Box 1588, Great Bend, Ks. 67530

PHONE # () _____ OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3771'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	152'	none
				5 1/2"	3770'	800'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with 5 sacks cement, sand to 3500' & 5 sacks cement. Shot pipe at 3016', 2017', 1514', 1009' & 800'. Pulled 25 joints of pipe. Plugged well with 2 hulls, 2 gel, 100 cement, 12 gel, 8 5/8 plug, & 70 sacks cement.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso


(employee of operator)

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of June, 1984



Irene Hoover
Notary Public

My Commission expires _____

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1984
CONSERVATION DIVISION
Wichita, Kansas

15-065-01332-00-00 41

ROTARY DRILLER'S LOG

E. K. Carey, Contractor
 Box 620
 McPherson, Kansas

Elevations: 2298 K.B.
 2295 D.F.

8-5/8" x 5 1/2" Head 7.10'
 below K. B.

Miron Goff "A" #2

Casing Record:

C, NW SE NW/4
 Sec. 3-8-24W
 Graham County, Kansas

8-5/8" @ 152' W/85 sks
 Reg. bulk cement and 100# cc.

Well Commenced: 1-25-55
 Well Completed: 2-4-55

5-1/2" 3770' W/100 sks
 Pozmix cement.

Contractor: E. K. Carey, Contractor, Rig #1, Box 620, McPherson, Kansas
 Geologist: Don Hollar, E. K. Carey Drlg. Co. 815 Central Bldg. Wichita

Figures Indicate Bottom of Formation K. B.

Cellar	7
Shale	45
Sand	95
Shale and shells	152
Shale	780
Shale	1040
Sand and shale	1260
Shale	1515
Sand and shale	1790
Shale and shells	1945
Anhydrite	1970
Shale and shells	2160
Shale and lime	2305
Shale and lime	2530
Lime and shale	2600
Lime	2710
Lime and shale	2810
Lime	3771 TD

Geologist Tops:

Heebner	3508
Lansing	3529
Base K.C.	3758
Rotary Total Depth	3771

Set 5 1/2" casing 3770 or 1 foot off bottom.

Centralizers - 3740, 3680, 3590 and 3560.

DST - 3565 - 3585 or 20' anchor, tool open 1 hr. strong blow thru out test. Closed 20 min. for BHP. Rec. 2220' gas 1270' oil no water. BHP 1330# FFP 460# IFP zero.

DST - 3680 - 3717 or 37' anchor, tool open 1 hr. good blow thru out test. Closed 20 min for BHP. Rec. 935' gas plus 600' oil. BHP 360# FFP 215#.

This is to certify that the above information is to the best of my knowledge true and correct.

SUBSCRIBED AND SWORN to before me this 7th day of February, 1955

E, K, CAREY CONTRACTOR

BY Herbert Rhoton
 Herbert Rhoton, Superintendent

[Signature]
 NP

My Commission Expires: November 13, 1956