

15-065-20319-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1970
CONSERVATION DIVISION
Wichita, Kansas

4-17-70

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Dave Rush Well No. 2

Location NE-SW-NW Sec. 34 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 15 Month 4 Year 1970

The above well was plugged as follows:

188'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement
thru DP from 1025' to 700'. Pulled DP to 215' and displaced 25 Sx. cement thru DP
From 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 4/17/70
INV. NO. 1744-W