

15-045-20295-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas
12/29/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Jones Well No. 1

Location SE-SE-SW Sec. 36 Twp. 8 Rge. (E) (W) 23

County Graham Total Depth 3840'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated.

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 7:30 AM Day 22 Month 12 Year 1969

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 840'.

Circulated hole with heavy mud. Pulled DP to 1070' and displaced 100 Sx. cement thru
DP from 1070' to 750'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 12/29/69

INV. NO. 1168-W