

15-065-01341-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 30 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-30-1970

Operator's Full Name Barnett Oil Company,

Complete Address 411 First National Bank Building, Wichita, Kansas.

Lease Name Nicholson Well No. 1

Location NW-NW-NW Sec. 12 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3823'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:15 PM Day 24 Month 11 Year 1970

The above well was plugged as follows:

122'--8 5/8" Surface casing, cement circulated with 100 Sx.  
3822'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to  
3801'.. Top perforations from 3741' to 3782'.

Sanded well back to 3725' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
(1055') and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed  
with 90 Sx. cement from 1100' to 800' then 15 sacks gel from 800' to 200' and finally  
60 Sx. cement from 200' to bottom of cellar. Maximum pump-in pressure--100#. Final  
shut-in pressure-50#. (Mudding and cementing by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Dick*  
Well Plugging Supervisor

INVOICED

DATE 12/1/70  
INV. NO. 2927-W