

15-065-02012-00-00

Form CP-3
Rev. 6-4-68

KANSAS

2
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Company,
Complete Address 411 First National Bank Building, Wichita, Kansas.
Lease Name Nicholson Well No. 3
Location CW/2 Sec. 12 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3825' RTD
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated Water Supply Well
Plugging Contractor Southwest Casing Pulling Company, Incorporated,
Address Box #364, Great Bend, Kansas. License No. 399
Operation Completed: Hour 6:30 PM Day 24 Month 11 Year 1970

The above well was plugged as follows:

154'--8 5/8" Surface casing, cement circulated with 125 Sx.
2018'--4 1/2" casing cemented on bottom with 150 Sx. Well plugged back to 1975'. 4 1/2" casing perforated in the Cedar Hills from 1637' to 1650'.
Attempted to push plug to 1600', plug stopped @ 1075'. Sanded back to 1040'. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 90 Sx. cement from 1100' to 800' then 15 sacks gel from 800' to 200' and finally 60 Sx. cement from 200' to bottom of ^{cellar} ~~surface~~. Maximum pump-in pressure--100#. Final shut-in pressure--50#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/1/70
INV. NO. 2929-W