

KANSAS

*10*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
10-7-1970

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Evans Well No. A-1

Location W/2-SE-SE Sec. 12 Twp. 8 Rge. (E) (W)24

County Graham Total Depth 3763'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 11:00 AM Day 5 Month 10 Year 1970

The above well was plugged as follows:

216'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru  
DP from 1025' to 700'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*  
Well Plugging Supervisor

DATE 10/7/70

INV. NO. 2645-W