

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 6 1967
2-6-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Incorporated.
Prairie Oil Field Service, Incorporated,

Complete Address: Box # 797, Great Bend, Kansas.

Lease Name Evans Well No. 1

Location NE-NE-SE Sec. 12 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3789

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box # 405, Chase, Kansas. License No. 346

Operation Completed: Hour 6:00 PM Day 30 Month 1 Year 1967

The Above well was plugged as follows:

190' -- 8 5/8" Surface pipe, cement circulated
3789' -- 5 1/2" Production casing cemented with 150 Sx. Well plugged back
to 3736'. Top perforations @ 3703'.

Sanded well back to 3685' and set 5 Sx. cement with dump bailer.
Pulled 5 1/2" casing to 720' and circulated heavy gel mud. (Used 25 Sx. gel)
Pulled 5 1/2" to 600' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to
210' and displaced 25 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge
@ 30' and 5 Sx. cement to bottom of cellar.

(Cementing and mudding operations performed by the Halliburton Company)

(Recovered 2300' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 2/7/67
INV. NO. 4729-W