

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 6 1965  
10-6-1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box 3797, Great Bend, Kansas.

Lease Name Hutton Well No. 2

Location CS/2-SE-NE Sec. 12 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3780

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 1:00PM Day 2 Month 10 Year 1965

The Above well was plugged as follows:

199'--8 5/8" Surface pipe, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 185', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 10/6/65

INV. NO. 1929-W