

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20433-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
4-16-71

Operator's Full Name Murfin Drilling Company,  
Complete Address 617 Union Center Building, Wichita, Kansas.  
Lease Name Evans Well No. 1  
Location SW-SW-NW Sec. 15 Twp. 8 Rge. (E) (W) 24  
County Graham Total Depth 3850'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Above  
Address      License No.       
Operation Completed: Hour 10:00 AM Day 13 Month 4 Year 1971

The above well was plugged as follows:

213'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru  
DP from 1075' to 750'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from  
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/16/71  
INV. NO. 3561-W

Signed: N. L. Nichols  
Well Plugging Supervisor