

KANSAS

*2*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20326-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
5-27-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name John O. Farmer, Incorporated,

Complete Address 370 West Wichita Avenue, Russell, Kansas.

Lease Name M. Covalt Well No. 1

Location CNE-SW Sec. 18 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3838'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 3:00 AM Day 23 Month 5 Year 1970

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 135 Sx.  
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru  
DP from 1050' to 725'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from  
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. D. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 5/28/70  
INV. NO. 1959-W