

B
KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20094-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1967
11-29-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Empire Drilling Company,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Law Well No. 1

Location CSW-NE Sec. 20 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3865'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Leben Drilling, Incorporated,

Address 815 Wichita Plaza, Wichita, Kansas. License No. _____

Operation Completed: Hour 9:45 PM Day 26 Month 11 Year 1967

The above well was plugged as follows:

208'--8 5/8" Surface pipe, cement circulate d with 175 Sx.
Dakota section from 850' to 1025'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 100 Sx. cement thru
DP from 1050' to 720'. Pulled DP to 230' and displaced 20 Sx. cement thru DP from
230' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 11-29-67

INV. NO. 6793-W