

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20298-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
1-5-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company.

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Keith Well No. 1

Location SE-SW-NW Sec. 20 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3875'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor L. J. Dreiling & Sons, Incorporated.

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 9:00 PM Day 1 Month 1 Year 1970

The above well was plugged as follows:

181'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru  
DP from 1075' to 750'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from  
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 1-5-70  
INV. NO. 1190-W