

15-065-20270-00-00

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1969

CONSERVATION DIVISION  
Wichita, Kansas

10-21-69

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas,

Lease Name Bell Well No. 1

Location SE-NE-SW Sec. 21 Twp. 8 Rge. (E) (W) 21

County Graham Total Depth 3870'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas, License No.       

Operation Completed: Hour 10:45 PM Day 19 Month 10 Year 1969

The above well was plugged as follows:

179'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1075' and displaced 100 Sx. cement thru  
DP from 1075' to 750'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from  
185' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/21/69

INV. NO. 697-W

Signed: W. L. Nichols  
Well Plugging Supervisor