



15-065-20295-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 29 1969
CONSERVATION DIVISION
Wichita, Kansas

12/21/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Jones Well No. 1

Location: SE-SE-SW Sec. 36 Twp. 8 Rge. (E)(W) 23

County: Graham Total Depth 3840' Oil Well

~~Gas Well~~ ~~Input Well~~ ~~SWD Well~~ ~~D & A~~ X ~~Lost Hole~~

Mr. Mickelson was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 840'.

Circulate hole with heavy mud. Pull DP to 1070' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Pichalski
Conservation Division Agent