



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Sharpe of Barnett Oil Company has this

date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Company,

Complete Address: 411 First National Bank Building, Wichita, Kansas.

Lease Name: Nicholson Well No. 1

Location: NW-NW-NW Sec. 12 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3823' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sharpe was instructed to plug the well as follows:

122'--8 5/8" Surface casing, cement circulated with 100 Sx.

3822'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3801'. Top perforations from 3741' to 3782'.

Sand well back to 3725' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Sx. cement, staged.

Very truly yours,

M. L. Nichols
Conservation Division Agent