



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas
11-30-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Deane Sharpe of Barnett Oil Company has this date requested permission to plug the following described well:

Mr. Sharpe guarantees payment of the plugging fee.

Operator's full Name: Barnett Oil Company.

Complete Address: 411 First National Bank Building, Wichita, Kansas.

Lease Name: Nicholson Well No. 3

Location: CW/2 Sec. 12 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3825' Oil Well

Gas Well Input Well SWD Well D & A Water Supply X
Loss Hole

Mr. Sharpe was instructed to plug the well as follows:

154'--8 5/8" Surface casing, cement circulated with 125 Sx.
2018'--4 1/2" casing cemented on bottom with 150 Sx. Well plugged back to
1975'. 4 1/2" perforated in the Cedar Hills from 1637' to 1650'.

Push plug to 1600', sand back to 1550' and set 5 Sx. cement with dump
bailer. Pull 5 1/2" and squeeze well with 5 sacks hulls, 30 sacks gel and
150 Sx. cement, staged.

Very truly yours,

Conservation Division Agent