



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1970
CONSERVATION DIVISION
Wichita, Kansas
10-7-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co., Inc., has this
date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Evans Well No. A-1

Location: W/2-SE-SE Sec. 12 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3763' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

216'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent