

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1967
2-6-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.
Chief Drilling Co. Inc.,
Operator's full Name: Prairie Oil Field Service, Inc.,

Complete Address: P. O. Box # 797, Great Bend, Kansas.

Lease Name: Evans Well No. 1

Location: NE-NE-SE Sec. 12 Twp. 8 Rge. (E)(W) 24

County Graham Total Depth 3789 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

190'--8 5/8" Surface pipe, cement circulated.
3789--5 1/2" Production casing cemented with 150 Sx. Well plugged back to 3736'. Top perforations @ 3703'.

Sand well back to 3685' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 720' and circulate heavy gel mud. Pull 5 1/2" to 600' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and displace 25 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge @ 30' and 5 Sx. cement to bottom of cellar.

Very truly yours,

H. R. Nichols
Conservation Division Agent