

State of Kansas



15-065-20094-00-00

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor  
WILLIAM I. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS - 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 29 1967  
11-29-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob White of Empire Drilling Company, has this  
date requested permission to plug the following described well:

Mr. White guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 750 4th National Bank Building, Wichita, Kansas.

Lease Name: Law Well No. 1

Location: CSW-NE Sec. 20 Twp. 8 Rge. (E)(W) 24

County Graham Total Depth 3865 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. White was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Dakota section from 850' to 1025'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.  
cement thru DP. Pull DP to 230' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent