



15-065-20298-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 5 1970
CONSERVATION DIVISION
Wichita, Kansas

1-5-70

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mickelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mickelson guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Keith Well No. 1

Location: SE-SW-NW Sec. 20 Twp. 2 8 Rge. (E)(W) 24

County: Graham Total Depth 3875' Oil Well

Gas Well Input Well SWD Well D-&-A X Lost Hole

Mr. Mickelson was instructed to plug the well as follows:

181'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent