



15-065-20270-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1969
CONSERVATION DIVISION
Wichita, Kansas

10-21-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mikelson of L. J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Mikelson guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company.

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Bell Well No. 1

Location: SE-NE-SW Sec. 21 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3870' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mikelson was instructed to plug the well as follows:

179'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 100 Sx. cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

K. S. Nichols
Conservation Division Agent