

State of Kansas



15-065-00716-00-01

FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1964
6-15-64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling has this date requested permission to plug the following described well:
D. R. Lauck Oil Co. Inc.,
Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: D. R. Lauck Oil Company, Incorporated,
Complete Address: 301 So. Broadway, Wichita, Kansas.
Lease Name: Kobler Well No. 1
Location: SE-SE-NW Sec. 24 Twp. 8 Rge. (E) (W) 24
County Graham Total Depth 3800 Oil Well
Gas Well Input Well SWD Well D & A X Lost Hole
Mr. Glenn was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated. 3800'--5 1/2" production casing, temperature survey showed top of cement @ 3050'. Well plugged back to 3777', top perforations @ 3740'.

Sand well back to 3730' and set 4 Sx. cement with dump bailer. Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 200' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,