

State of Kansas



15-063-20762-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1975

CONSERVATION DIVISION
Wichita, Kansas

6-25-75

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Co has this date requested permission to plug the following described well:

Mr. Ralph Niernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Co

Complete Address: 617 Union Center Wichita Ks.

Lease Name: Gates Well No. #1

Location: SW-SE-SW Sec. 25 Twp. 8 Rge. 24 (E) (W) W

County: Graham Total Depth 3940 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ralph Niernberger was instructed to plug the well as follows:

Pump down drill stem.

70 sx cem 50/50 Pozmix 6% Gel @ 1100'

20 " " " " " " " 135'

Build Bridge To 40'

10 sx cem 50/50 Pozmix 6% Gel. 40' to O'

Very truly yours,

Richard Balthasar
Conservation Division Agent