

State of Kansas



FORM - CP-2
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1964
6-1-1964
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Hicks of Southwest Csg Pulling Co. has this date requested permission to plug the following described well:
Imperial Oil of Kansas
Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil of Kansas,

Complete Address: Box #97, WaKeeney, Kansas.

Lease Name: Kobler Well No. A-1

Location: NW-SE-SW Sec. 26 Twp. 8 Rge. (E) (W) 24

County Graham Total Depth 3916 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hicks was instructed to plug the well as follows:

230'--8 5/8" Surface pipe, cement circulated with 150 Sx.
3915'--4 1/2" production casing cemented with 125 Sx. Well plugged back to 3800. Top perforations 3745 to 3749.

Sand well back to 3735 and set 3 Sx. cement with dump bailer.
Pull 4 1/2" to 660' and circulate heavy gel mud. Pull 4 1/2" to 540 and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 210' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. D. Nichols