

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
12-20-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Lindsay guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holly North LKC Unit Well No. 101

Location: SW-SW-NW Sec. 28 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3888' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lindsay was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3888'--5 1/2" Production casing cemented on bottom with 125 Sx. Well  
plugged back to 3877'. Top perforations @ 3733'.

Push plug to 3500', sand back to 3475' and set 5 Sx. cement with dump  
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks  
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent