

15-065-02708-00-00

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 14 1974  
2-14-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: 710 Sutton Place, Wichita, Kansas.

Lease Name: Holly LKC Unit North Well No. 201

Location: SW-NW-SW Sec. 28 Twp. 8 Rge. (E)(W) 2h

County: Graham Total Depth 3886' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Wasinger was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3886'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug-back indicated. Top perforations from 3732' to 3736'. 5 1/2" has been squeezed @ 1720' with 150 Sx. cement.

Sand well back to 3720' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

*W. J. Nichols*  
Conservation Division Agent