



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 20 1971

CONSERVATION DIVISION  
Wichita, Kansas

12-20-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Lindsay guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holly North LKC Unit Well No. 304S

Location: SW-NE-NE Sec. 29 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3900' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lindsay was instructed to plug the well as follows:

225 KCC  
241

216'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3898'--5 1/2" Production casing cemented on bottom with 125 Sx. No plug back nor perforations indicated.

Push plug to 3500', sand back to 3475' and set 5 Sx. cement with dump bailer. Pullcasing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

Conservation Division Agent