

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas
5-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsay of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Lindsay guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holley LKC Unit-North Well No. 301

Location: CSW-SE-NE Sec. 29 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3920' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lindsay was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated.

3910'--5 1/2" Production casing, cemented on bottom with 125 Sx. Well plugged back to 3690'. Hole in 5 1/2" casing @ 3295'.

Push plug to 3200'. Build sand beidge to 3175' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement staged.

Very truly yours,

W. L. Nichols

Conservation Division Agent