



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1974
2-14-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company.

Complete Address: 710 Sutton Place, Wichita, Kansas.

Lease Name: Holly LKC Unit-North Well No. 302-W

Location: NE-SE-NE Sec. 29 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3900' Oil Well X

Gas Well Input Well X ^{KCC ZAP} SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

195'--8 5/8" Surface casing, cement circulated with 175 Sx.
3900'--5 1/2" Production casing cemented on bottom with 125 Sx. Well
plugged back to 3770'. Top perforations from 3742' to 3744'.

Squeeze well with 5 sacks hulls, 30 sackz gel and 150 Cu. Ft. cement.

Staged.

Very truly yours,

W. L. Dickson
Conservation Division Agent