

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas

5-20-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: P. O. Box #922, Great Bend, Kansas.

Lease Name: T. L. Smith Well No. 6

Location: NE-SW-SE Sec. 30 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3960' Oil Well X

Gas Well Input-Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.
3959'--7" OD Production casing cemented on bottom with 150 Sx. well
plugged back to 3955'. Top perforations from 3940' to 3944'.

Sand well back to 3930' and set 6 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 5 sacks hulls, 35 sacks gel and 175 Sx.
cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent