



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1973
10-23-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Fuzzell of Petroleum Management, Inc., has this

date requested permission to plug the following described well:

Mr. Fuzzell guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 KSB & T Building, Wichita, Kansas.

Lease Name: Holley Unit Well No. 2-1

Location: SW-SW-SW Sec. 30 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 4005' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Fuzzell was instructed to plug the well as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.
4004'--7" Production casing cemented on bottom with 150 Sx. Well
plugged back to 3971'. Top perforations from 3932' to 3955'. DV Tool
set @ 2183' with 150 Bbl. Black-Magic to surface.

Sand well back to 3920' and set 6 Sx. cement with dump bailer. Pull
7" casing and squeeze well with 7 sacks hulls, 50 sacks gel and 210 Cu.
Ft. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent