



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION

FEB 25 1974  
2-25-1974  
CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this

date requested permission to plug the following described well:

Mr. Rine guarantees payment of the plugging fee.Operator's full Name: Petroleum Management, Incorporated,Complete Address: 1515 KSB&T Building, Wichita, Kansas.Lease Name: Holly Unit Well No. 2-2Location: SW-SE-SW Sec. 30 Twp. 8 Rge. (E)(W) 24County: Graham Total Depth 3948' Oil Well XGas Well      Input Well      SWD Well      D & A      Lost Hole     Mr. Rine was instructed to plug the well as follows:

325'--10 3/4" Surface casing, cement circulated with 250 Sx.  
3944'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool  
@ 2180' with Chem-Pak circulated to surface, no plug-back indicated, top  
perforations from 3925' to 3928'.

Sand well back to 3900' and set 6 Sx. cement with dump bailer. Pull 7"  
casing and squeeze well with 7 sacks hulls, 50 sacks gel and 120 Sx.  
Halliburton Lite Cement, staged.

Very truly yours,

*H. L. Nichols*  
 Conservation Division Agent