



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1974
2-25-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this date requested permission to plug the following described well:

Mr. Rine guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 KSB&T Building, Wichita, Kansas.

Lease Name: Holly Unit Well No. 2-3

Location: NE-SW-SW Sec. 30 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3984' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Rine was instructed to plug the well as follows:

318 ^{KCC ZAP} 310'--10 3/4" Surface casing, cement circulated with 250 Sx.
3983'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool set @ 2212' with Black Magic circulated to surface Top perforations from 3959' to 3964'.

Sand well back to 3940' and set 6 Sx. cement with dump bailer. Pull 7" casing and squeeze well with 7 sacks hulls, 50 sacks gel and 120 Sx. Halliburton Lite Cement, staged.

Very truly yours,

R. L. Nichols
Conservation Division Agent