

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
5-20-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: T. L. Smith, Holley Unit #2 Well No. 4

Location: NE-SE-SW Sec. 30 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3978' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

318'--10 3/4" Surface casing cement circulated with 210 Sx.  
3972'--7" OH Production casing cemented on bottom with 100 Sx. Well plugged back to 3965'. Top perforations from 3954' to 3959'.

Sand well back to 3940' and set 6 Sx. cement with dump bailer. Pull 7" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 175 Sx. cement, staged.

Very truly yours,

W. L. Fisher  
Conservation Division Agent