



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1974
2-25-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rine of Petroleum Management, Inc., has this

date requested permission to plug the following described well:

Mr. Rine guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 KSB & T Building, Wichita, Kansas.

Lease Name: Holly Unit Well No. 2-5

Location: SW-NE-SW Sec. 30 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3985' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Rine was instructed to plug the well as follows:

318'--10 3/4" Surface casing, cement circulated with 210 Sx.
3981'--7" OD Production casing cemented on bottom with 100 Sx. DV Tool
set @ 2207' with Black Magic to surface. Well plugged back to 3975'.
Top perforations from 3961' to 3964'.

Sand well back to 3950' and set 6 Sx. cement with dump bailer. Pull 7"
casing and squeeze well with 7 sacks hulls, 50 sacks gel and 120 Sx.
Halliburton Lite Cement; Staged.

Very truly yours,

H. G. Dickole
Conservation Division Agent