

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1972
4-17-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clark of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Clark guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Keith Well No. B-4 Tract #9, Well #4

Location: SE-SW-SW Sec. 32 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3985' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Clark was instructed to plug the well as follows:

215'-- 8 5/8" Surface casing, cement circulated with 175 Sx.
3985'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3973'. Top of perforations @ 3795'. 5 1/2" squeezed @ 2550' w/400 Sx.
Push plug to 3750' sand back to 3725' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, Staged.

Very truly yours,

A. G. Nichols
Conservation Division Agent