

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1971
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: Box #922, Great Bend, Kansas.

Lease Name: Keith Well No. B-5

Location: CS/2-NW-NW Sec. 32 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 3970' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 175 Sx.
3969'--5 1/2" Production casing cemented on bottom with 100 Sx. Well plugged back to 3939'. Top perforations from 3920' to 3924'. 5 1/2" has been squeezed @ 1850'.

Sand well back to 3900' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement. staged.

Very truly yours,

Conservation Division Agent