

State of Kansas



15-065-02213-00-01

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Co., has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holley LKC Unit Well No. ~~101-11~~ 101/W^{ICCC} 2AP

Location: NE-SE-NW Sec. 33 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 4010 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated.

4004'--4 1/2" Production casing cemented on bottom with 100 Sx. Top perforations @ 3928'.

Sand well back to 3900' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement staged.

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1969

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

7/1/69

W. L. Nichols

Conservation Division Agent