



02762
15-065-02972-00-22 01

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1968
CONSERVATION DIVISION
Wichita, Kansas

6/27/68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holley LKC Unit Well No. 102-W

Location: S/2-SW-NW Sec. 33 Twp. 8 Rge. (E)(W) 24

County: Graham Total Depth 4025 Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

179'--8 5/8" Surface pipe, cement circulated with 150 Sx.
4025'--5 1/2" Production casing cemented on bottom with 100 Sx. Well Plugged back to 4006' Injection zones from 3948 to 3953 and 3966' to 3970'. 5 1/2" squeezed in Cedar Hills with 225 Sx. cement and 227 Sx. cement.
Run 2" tubing to bottom and displace 20 Sx. cement thru Tubing from 4006' to 3846'. Pull tubing to 3846' and displace 20 Sx. gel thru tubing from 3846' to 1800' then 125 cenebt from 1800' to 800' then 8 gel from 800' to 40' and finally 5 Sx. cement from 40' to bottom of cellar.

Very truly yours,

Conservation Division Agent