

State of Kansas



15-065-02766-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Co., has this
date requested permission to plug the following described well:

8/16/67

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Holley LKC Unit Well No. 204

Location: NE-NW-SE Sec. 33 Twp. 8 Rge. (E)(W) 24

County Graham Total Depth 3986 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

216'--8 5/8" Surface pipe, cement circulated with 200 Sx.
3986'--5 1/2" Production casing cemented with 100 Sx. DV tool
@ 2118' with 100 Bbl. Chempac. Tubing and rods lost in hole
@ 2164', unable to fish. Dakota section from 850' to 1050'.

Squeeze well with 18 Sx. gel with 5 sacks hulls, follow with
100 Sx. cement then 10 Sx. gel and follow with 20 Sx. cement,
then 3 Sx. gel and follow with 5 Sx. cement.

Very truly yours,

A. L. Fisher
Conservation Division Agent