

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20094-00-01
Spot: NENESW Sec/Twnshp/Rge: 31-20S-13W
2166 feet from S Section Line, 3168 feet from E Section Line
Lease Name: MORRIS OWWO Well #: 1
County: BARTON Total Vertical Depth: 3723 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3628	0	w/150 sxs cmt
SURF	8.625	250	0	w/175 sxs cmt

121.00

Well Type: EOR UIC Docket No: E21504.1 Date/Time to Plug: 04/16/2008 12:30 PM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE STOPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 4% gel - 600# hulls - 5 sxs gel.
Junk in the hole at 3228'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2008 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3228' - pumped 5 sxs gel with 150# hulls.
Pumped 50 sxs cement with 100# hulls.
Pulled to 1550' - pumped 50 sxs cement with 100# hulls.
Pulled to 800' - pumped 110 sxs cement with 200# hulls - circulated to the top.
Pulled tubing - tied to and pumped 15 sxs cement.
S.I.P. 250#.

Perfs:

INVOICED
DATE 4-28-08
INV. NO. 2008061629

Remarks: COPELAND ACID AND CEMENTING COMPANY-TICKET #33423.

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

APR 25 2008

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

APR 21 2008

PT

BROUGHER OIL INC
 P.O. DRAWER 1367
 GREAT BEND, KS 67530


#1 MORRIS "OWWO"

31-20-13W
 50'S&50'W,
 NE NE SW

CONTR MOHAWK DRILLING INC CTY BARTON

GEOL _____ FIELD HISS SO

E 1905 KB E CM 11/10/79 CARD ISSUED 6/12/80 IP SWDW ARB OH 3445-3595



15-009-20,094-A

LOG	TOPS	DEPTH	DATUM
ANH		782	+1123
HEEB		3171	-1266
TOR		3191	-1286
DOUG		3211	-1306
BR LM		3285	-1380
LANS		3297	-1392
B KC		3512	-1607
CONG		3527	-1622
ARB		3569	-1664
LTD		3584	-1679
RTD		3595	-1690

OLD INFO; OPERATOR WAS DEAN & CLARK,
 INC, #3 BENJAMIN 'A' TWIN, 8/11/67,
 SET 8" 252, COMPLETED AS D&A/ARB
 8/24/67

- DST (1) 3303-40/75", 60' GIP, 15M O/S
 BHP 310-275#, FP 35-35#
- DST (2) 3356-3400/90", 660' SW, BHP
 825-810#/30", FP 100-465#
- DST (3) 3446-73/70", 30' M O/S, BHP
 760-320#/30", FP 25-25#
- DST (4) 3531-80/1', 10' M, BHP 165-
 35#/30", FP 35-35#
- DST (5) 3385-95' (SP) TOOL PLUG

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS