

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21134-00-00
Spot: NESWNW Sec/Twnshp/Rge: 36-16S-29W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: JAMES Well #: 1
County: LANE Total Vertical Depth: 4243 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 221 N MAIN STE 300 PO BOX 2758
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2030		
CIBP		4200		
DVT		2047		CEMENTED TO SURFACE
PROD	5.5	4600	0	WITH 175 SX CMT
SURF	8.625	217		WITH 150 SX CMT

137.90

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 04/16/2008 9:30 AM
Plug Co. License No.: 5144 Plug Co. Name: MULL DRILLING COMPANY, INC.
Proposal Rcvd. from: TONY DUMMLER Company: MULL DRILLING COMPANY, INC. Phone: (316) 264-6366

Proposed Plugging Method: MIX 300# HULLS IN FIRST OF CMT & FILL CASING TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/16/2008 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

MIX 300# HULLS IN FIRST OF CMT. PUMP 200 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO BACKSIDE & PUMPED 50 SX CMT. PRESSURED TO 50#.

Perfs:

INVOICED
DATE 4-28-08
INV. NO. 2008061628

RECEIVED
KANSAS CORPORATION COMMISSION
APR 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED
APR 21 2008
KCC Dodge City

Signed

Michael Maier
(TECHNICIAN)