

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24602-00-00

Spot: NWNE

Sec/Twnshp/Rge: 16-16S-24W

700 feet from N Section Line, 1850 feet from E Section Line

Lease Name: ROLF

Well #: 1

County: NESS

Total Vertical Depth: 4627 feet

Operator License No.: 30742

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1871		WITH 170 SX CMT
PROD	5.5	4601	0	WITH 175 SX CMT
SURF	8.625	261		WITH 175 SX CMT

156.38

Well Type: DH

UIC Docket No:

Date/Time to Plug: 04/02/2008 4:00 PM

Plug Co. License No.: 32382

Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: PATRICK J. GERSTNER

Company: PALOMINO PETROLEUM

Phone: (316) 799-1000

Proposed
Plugging
Method:

PUMP 40 SX CMT & 200# HULLS ON BOTTOM. GEL SPACER TO 1800'. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/02/2008 6:00 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMPED 40 SX CMT & 200# HULLS-15 SX GEL SPACER -175 SX CMT. PUMP 175 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 900#. TIED ONTO BACKSIDE AND PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4520	4524		
4488	4492		
4480	4484		

INVOICED

DATE 4-28-08

INV. NO. 2008061630

RECEIVED
KANSAS CORPORATION COMMISSION


APR 24 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

Michael J. Maier

(TECHNICIAN)

Form 12-273

PS