

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-00142-00-03
Spot: SESENE Sec/Twnshp/Rge: 10-26S-15W
2970 feet from S Section Line, 330 feet from E Section Line
Lease Name: GEREKE Well #: 7W 01
County: PRATT Total Vertical Depth: 4605 feet

Operator License No.: 30560
Op Name: CROCKETT OIL AND GAS, INC.
Address: 202 N. MAIN
SHARON, KS 67138

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4302	2008	
SURF	13.38	275		

149.66

Well Type: EOR UIC Docket No: E27311.1 Date/Time to Plug: 04/22/2008 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 983-2537

Proposed Plugging Method: PULL TBG OUT OF HOLE. SAND BOTTOOM TO 3930' & 5 SX CMT WITH BAILER. RIP PIPE AT FREEPOINT AND PULL OUT OF HOLE. RUN TBG BACK IN TO 1000'. PUMP 15 SX GEL & 50 SX CMT. PULL TBG TO 300' & PUMP 100 SX CMT. PULL TBG TO 40' & PUMP 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 04/22/2008 11:40 AM

Witness Type: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PACKER LEFT IN HOLE @ 3906'. SANDED TO 3900' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1000' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 300' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 75 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3984	4112		

INVOICED

DATE 5-1-08
INV. NO. 2008061642

RECEIVED
KANSAS CORPORATION COMMISSION


APR 28 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

Form CP-28

RLT