

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21447-00-00
Spot: NENWNE Sec/Twnshp/Rge: 9-14S-15W
4936 feet from S Section Line, 1724 feet from E Section Line
Lease Name: SANDER Well #: 1
County: RUSSELL Total Vertical Depth: 3270 feet

Operator License No.: 3134
Op Name: MORRIS, TERRY E. DBA G L M COMPA
Address: PO BOX 193
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3274	0	w/300 sxs cmt
SURF	8.625	218	0	w/150 sxs cmt <u>106.28</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 16 sxs gel - 400# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2008 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality Well Service sanded off bottom to 3168' and topped with 5 sxs cement.
Wanted to pull 5 1/2" casing - found to be cemented in - backside full of cement.
Ran tubing to 3100'. Quality rigged to tubing - pumped 16 sxs gel.
Pulled tubing to 1500'. Rigged to tubing - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls mixed into circulate cement to surface.
Pulled tubing - topped with 25 sxs - hole standing full.

Perfs:

INVOICED
DATE 5-1-08
INV. NO. 2008061646

RECEIVED
KANSAS CORPORATION COMMISSION
APR 30 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE CEMENTING COMPANY-TICKET #1928.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

APR 28 2008

[Signature]

SOLAR PETROLEUM, INC.
1099 18TH ST. #2900
DENVER, CO 80202

REPLACEMENT CARD
#1 SANDER

9-14-15W
NE NW NE

CONTR REVLIN DRILLING INC.

CTY RUSSELL

GEOL GLENN D. TRACY

FIELD GORHAM

ELV 1870 KB SPD 5/19/80 CARD ISSUED

10/16/80

IP P 10 BOPD

LKC - INTV NA

API 15-167-21,447

DRLRS	Tops	Depth/Datum
ANH		898 + 972
B/ANH		939 + 931
*HOW		2688- 818
*TOP		2748- 878
PLATTSM		2895-1025
*HEEB		2978-1108
*TOR		2999-1129
*LANS		3032-1162
KC		3090-1220
ARB		3128-1258
GRAN		3235-1365
*GR WSH		3257-1387
RTD		3270-1400
*SAMPLE TOPS		

8 5/8 " 218 / 150SX, 5 1/2 " 3274 / 300SX

NO DST'S

MICT - CO, PF (LKC) INTV NA, SWB DWN, SO, SET 2 3/8 " TBG
AT 3200', POP (DEPTH NOT RPTD) - NO OTHER INFO RELEASED
BY OPERATOR

**CORRECTION & INFO RELEASED: 4/4/85 - ORIGINALLY FIRST RE-
PROTOD AS CRUDE PRODUCERS INC., WAS OIL WELL - TIGHT
HOLE**

COPYRIGHT 1985
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS