

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21268-00-02
Spot: NESE Sec/Twnshp/Rge: 4-29S-12W
1980 feet from S Section Line, 660 feet from E Section Line
Lease Name: NEEL Well #: 1
County: PRATT Total Vertical Depth: 4350 feet

Operator License No.: 30705 •
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3610		WITH 2 SX CMT
CIBP		3694		
CIBP		4041		
CIBP		4254		
PROD 5.5		4350	725	WITH 225 SX CMT
SURF 8.625		389		WITH 275 SX CMT

141.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2008 12:45 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LUKE DYKES Company: YOUNGER ENERGY Phone: _____

Proposed Plugging Method: ACCORDING TO KCC INSTRUCTIONS. CIBP @ 3610', PULL CSG., PLUG @ 800' W/50 SXS, PLUG @ 420' WITH 50 SXS, PLUG @ 40' W/ 15 SXS OF 60/40 CEMENT W/ 4% GEL; 12 SXS GEL ON THE SIDE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2008 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3610' & PUT 2 SX CMT ON TOP THROUGH DUMP BAILER. LAID DOWN CASING & RAN 2 3/8" TBG IN TO PLUG. 1ST PLUG AT 715' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4263	4271		
4228	4230		
4010	4016		
3652	3659		

INVOICED

DATE 5-1-08


INV. NO. 2008061651

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

APR 30 2008

Plugged through: TBG



Signed Stephen J Pfeifer
(TECHNICIAN)

District: 01

CONSERVATION DIVISION
WICHITA, KS

Form CP
[Signature]